

工 事 名：令和6年災第6096号 市道清土線道路災害復旧工事 工事場所：輪島市 門前町浦上地内					数 量 調 書(1/1)		
工 種	規 格	寸 法	単位	数 量	計 算 式		摘 要
土 工							
	掘 削		m3	40	38.89	= 38.89 m3	
	残 土 処 分		m3	40	38.89	= 38.89 m3	
舗 装 工							
	表 層 工	密粒度As (20F) t =5cm	m2	405	405.44	= 405.44 m ²	
	不陸整正	粒調碎石 (M-30) t =3cm	m2	17	16.60	= 16.60 m ²	
	上層路盤工	粒調碎石 (M-30) t =10cm	m2	389	388.84	= 388.84 m ²	
取 壊 工							
	舗装切断工		m	17	16.60	= 16.60 m	
	アスファルト舗装版 破 碎 工		m2	410	405.44	= 405.44 m2	
	アスファルト殻運搬		m3	20	V= 0.05 x 405.44	= 20.27 m3	
	アスファルト殻 処 分 費		t	48	W= 20.27 x 2.35	= 47.63 t	
							輪 島 市

工 事 名：令和6年災第6096号 市道清土線道路災害復旧工事
工事場所：輪島市 門前町浦上地内

(1/1)

土 量 計 算 書

測 点	単距離						上層路盤					下層路盤		区画線		舗装版切断	摘 要
		幅 員	平 均	掘削深	掘削土量	路床盛土	舗装面積	不陸整正	t=10cm	t=15cm	t=10cm	t=15cm	t=19cm	白 15cm	白 45cm		
No. 0	—	2.5	—		—											2.50	①区間
No. 1	1.0	2.5	2.50	0.00	0.00		2.50	2.50									
No. 22.3	21.3	2.5	2.50	0.10	5.33		53.25		53.25								
No. 30.8	8.5	2.3	2.40	0.10	2.04		20.40		20.40								
No. 35.2	4.4	2.3	2.30	0.10	1.01		10.12		10.12								
No. 36.2	1.0	2.3	2.30	0.00	0.00		2.30	2.30								2.30	
No. 57.0	—	2.3	—		—											2.30	②区間
No. 58.0	1.0	2.3	2.30	0.00	0.00		2.30	2.30									
No. 58.7	0.7	2.0	2.15	0.10	0.15		1.51		1.51								
No. 68.5	9.8	2.3	2.15	0.10	2.11		21.07		21.07								
No. 69.5	1.0	2.3	2.30	0.00	0.00		2.30	2.30								2.30	
No. 87.0	—	2.2	—		—											2.20	③区間
No. 88.0	1.0	2.2	2.20	0.00	0.00		2.20	2.20									
No. 96.4	8.4	2.1	2.15	0.10	1.81		18.06		18.06								
No. 103.9	7.5	4.7	3.40	0.10	2.55		25.50		25.50								
No. 108.0	4.1	2.5	3.60	0.10	1.48		14.76		14.76								
No. 110.6	2.6	2.5	2.50	0.10	0.65		6.50		6.50								
No. 111.6	1.0	2.5	2.50	0.00	0.00		2.50	2.50								2.50	
No. 135.0	—	2.5	—		—											2.50	④区間
No. 136.0	1.0	2.5	2.50	0.00	0.00		2.50	2.50									
No. 141.0	5.0	2.3	2.40	0.10	1.20		12.00		12.00								
No. 147.2	6.2	3.3	2.80	0.10	1.74		17.36		17.36								
No. 148.7	1.5	3.6	3.45	0.10	0.52		5.18		5.18								
No. 168.5	19.8	2.4	3.00	0.10	5.94		59.40		59.40								
No. 180.2	11.7	2.7	2.55	0.10	2.98		29.84		29.84								
No. 204.7	24.5	2.6	2.65	0.10	6.49		64.93		64.93								
No. 214.2	9.5	3.5	3.05	0.10	2.90		28.98		28.98								
合 計	152.5	2.6			38.89	0.00	405.44	16.60	388.84	0.00	0.00	0.00	0.00	0.00	0.00	16.60	

上層路盤工 計 388.84 m2
下層路盤工 計 0.00 m2