

塚田町仮置場

	W1	B1	W1	B1	H	
全残土量	{(34.5	× 32.1)	+ (22.5	× 26.1)}	/2 × 4	= 3,389 m3
搬出土量	{(34.5	× 17.6)	+ (22.5	× 17.6)}	/2 × 4	= 2,006 m3
搬出後残土量	{(34.5	× 14.5)	+ (22.5	× 8.5)}	/2 × 4	= 1,383 m3
搬出地山土量	1,672					m3